

SNDT Women's University

1, Nathibal Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथोबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

Estate Dept./2020-21 /(Not.6)/180

March 31, 2021

Sub: Quotation for Providing and fixing gully trap, Inspection Chamber and plinth protection to building of special education dept. at SNDT Women's University, Juhu Campus.

Madam/Sir,

Sealed quotations are invited for Providing and fixing gully trap, Inspection Chamber and plinth protection to building of special education dept. at SNDT Women's University, Juhu Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the Office of "The Registrar" at Churchgate campus on or before 8th April 2021 Contractor should submit their.

- i) GST No.
- ii) PAN no.
- iii) Client List,
- iv) Company profile,
- v) Last 3 years audited profit lost statement along with Quotation

Quotation should be submitted in closed envelop and on top write the subject.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

02
RA

Meena
31.3.21
(Dr. Meena Kute)
Registrar(Addl.Charge)

(Offer should filled on letter head)

Annexure A

To,
The Registrar
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation Provision for Providing and fixing gully trap , Inspection Chamber and plinth protection to building of special education dept. at SNDT Women's University, Juhu Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of Item	Qty	Unit	Rate	Amount
01	Providing and fixing 15cm x 10cm salt glazed stoneware gully trap in cement concrete 1:4:8 outside the building including cast iron grating in the sink, connecting glazed stoneware pipe, brick masonry chamber with cast iron lid and cast iron grating for the gully trap.	6.00	No.		
02	Providing and constructing Brick Masonry Inspection Chamber 90cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W.pipes, Brick Masonry, plastering from inside and C.I. lid cover of 75 kg with lid and frame fixed in cement concrete.	5.00	No.		
03	Providing and laying P.V.C. 160 mm Soil pipe in proper line, level and slope including necessary collars, Excavation, laying , fixing with colars in cement mortar 1: 1 and refilling the trench complete.	42.00	Rmt.		
04	Providing and laying P.V.C. 110 mm Soil pipe 6 Kg/cm ² pressure in proper line, level and slope including necessary collars, Excavation, laying , fixing with collars in cement mortar 1: 1 and refilling the trench complete	12.00	Rmt.		
05	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Manual Means	27.300	Cum.		

SNDT Women's University

1, Nathibal Thackersey Road,
Mumbai 400 020
Phone: +91 22 2203 1879
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ
१, नाथीबाई ठाकरसी मार्ग
मुंबई ४०० ०२०
Telegram: UNIWOMEN
Website: sndt.ac.in

06	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	18.200	Cum.		
07	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, plywood/steel formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	13.650	Cum.		
08	Providing rough cast cement plaster externally in two coats to concrete, brick or stone masonry surfaces in all positions with base coat of 12 to 15 mm thick in C.M. 1:4 and rough cast treatment 12mm thick in proportion 1:1 1/2:3 including scaffolding and fourteen days curing complete.	16.00	Sqm.		
09	Manually Clearing the Chocks from underground drainage line including Inspection with the help of required tools for proper functioning line chamber etc. complete.	44.00	Rmt.		
	Total				

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

Name of Company

Signature of the Proprietor

Date:

Note: Enclose GST number, PAN number, declaration if GST is not applicable