

**SNDT Women's University**  
1, Nathibai Thackersey Road,  
Mumbai 400 020  
Phone: +91 22 2203 1879  
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ  
१, नाथीबाई ठाकरसी मार्ग  
मुंबई ४०० ०२०  
Telegram: UNIWOMEN  
Website: sndt.ac.in

Estate Dept./2022-23/347

October 14, 2022

**SUB: Quotation for Repair & Renovation work of Management Flat at S.N.D.T. Women's University, Pune Campus.**

**Madam/Sir,**

Sealed quotations are invited for repair & renovation work of Management Flat at S.N.D.T. Women's University, Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **07 December 2022**. Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

**a) Technical Bid**

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

**b) Financial Bid**

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

**The University reserves the right to reject any or all quotations without assigning any reasons thereof.**

Regards,

Prof. Vilas D. Nandavadekar

**Registrar**

**(Offer should filled on letter head)**  
**Annexure A**

To,  
The Registrar  
SNDT Women's University,  
Churchgate, Mumbai

**Sub: Quotation for Repair & Renovation work of Management Flat at S.N.D.T. Women's University, Pune Campus.**

**Respected Madam/Sir,**

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

<b>Sr. No</b>	<b>Description of Item</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
1	Removing cement tiles, ormarble or polished Shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete	31.00	Sqm.		
2	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	65.00	Sqm.		
3	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Manual Means	32.00	Cum.		
4	Providing dry/trap/granite/quartzite/gneiss rubble stone soling 15 cm to 20cm thick including hand packing and compacting etc. complete.	16.00	Cum.		
5	Filling in plinth and floor swith contractors material/brought from outside and approved by Engineer in charge in layers of 15cm to 20cm including watering and compaction etc.complete.	16.00	Cum.		
6	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for bed blocks, foundation blocks and such other items including bailing out water, plywood/steel formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With natural	19.00	Cum.		

	sand/V.S.I. quality Artificial Sand				
7	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	65.00	Sqm.		
8	Providing and applying required coats of a water based Evercrete Deep Penetrating Sealer (DPS) on cement concrete surface like roads, beams, and columns, plastered walls, basements, roofs, potable water tanks etc to react with cement and to penetrate concrete structure thereby making it resistant to chemicals / chlorides water to make it dust proof and to act as a water resistant at the same time which Strengthens the treated surface and reduce the curing period etc complete. - Note -- for item no. 7 to 4 prior approval of Superintending Engineer will be necessary	65.00	Sqm.		
9	Machine polishing to cement/marble mosaic tiled flooring or any other type of flooring including cleaning, washing, etc. complete.	260.00	Sqm.		
10	Providing and fixing solid core flush door shutter commercial in single leaf 32 mm thick without ventilator commercial type of exterior grade as per detailed drawings with wrought iron hold fast, stainless steel fixtures and fastenings and handles on both sides and finishing with oil painting 3 coats complete.	10.00	Sqm.		
11	Providing and fixing P.V.C. Rain water pipes of 110mm outer diameter and having wall thickness of 2.2 to 2.7 mm confirming to I.S. 13592-1992 including proper rainwater receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on wall using approved wooden cleats projecting 25mm to 40mm from face of wall a fixing with clips of approved quality and number ,filing the joint using rubber gasket with solvent cement and properly resting the shoe of pipes on C.C. or masonry blocks, including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. All the P.V.C. fittings and additional 2 piece socket clips shall be got approved from engineer in charge etc. complete. (The contractor shall give 3 yrs guarantee bond for payment)	22.00	Rmt.		

12	Lowering down the debris obtained from breaking and removing the cement plaster/burnt brick masonry of the first floor by any means without causing dust nuisance and damage to structure, stacking the same as and where directed including cleaning the site complete.	14.00	Cum.		
13	Removing old paint from steel and other metal surfaces and making the surfaces even with hand scrapping, scaffolding etc. complete.	69.00	Sqm.		
14	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	610.00	Sqm.		
15	Providing and applying Two coats of wall care Putty of 2mm thickness for plastered surface and 5-6mm thickness finished concrete surface to Ceiling and Walls to prepare surface even and smooth of Brands BIRLA WHITE, BERGER, BISION, J.K., make, etc complete. a) For plastered walls/ceiling 2mm	325.00	Sqm.		
16	Providing and applying priming coat over new/old steel and other metal surfaces including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and scoured with wire brushes, fine steel wool, scrappers and sand paper, scaffolding etc. complete.	679.00	Sqm.		
17	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface. (Excluding primer coat) etc. complete.	610.00	Sqm.		
18	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	69.00	Sqm.		
	Net Total				
	Taxes will be paid at actual at the prevailing time.				
	Total				