SNDT Women's University 1, Nathibai Thackersey Road, Mumbai 400 020 Phone: +91 22 2203 1879 Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ १, नाथीबाई ठाकरसी मार्ग मुंबई ४०० ०२० Telegram: UNIWOMEN Website: sndt.ac.in

Estate Section/2023-24/241

October 13th , 2023

SUB: Quotation to Repair to W.C. / bath units of 1st floor for Students at New Home Science bldg. at S.N.D.T. Women's University, Pune Campus. Madam/Sir,

Sealed quotations are invited for Quotation to Repair to W.C./ bath units of 1st floor for Students at New Home Science bldg. at S.N.D.T. Women's University, Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **27th October**, **2023** Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop. Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant
- **B)** Financial Bid
 - vii. Mentioning including all taxes
 - viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,

Prof. Vilas D. Nandavadekar

(Offer should filled on letter head) Annexure A

To,

The Registrar, SNDT Women's University, Churchgate, Mumbai

Sub: Quotation for Repair to W.C./ bath units of 1st floor for Students at New Home Science bldg. at S.N.D.T. Women's University, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Removing cement tiles, or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complet	98.00	Sqm		
2	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc. complete.	75.00	Sqm		
3	Removing doors and windows with frames and stacking the materials as directed with all leads, lifts etc. complete.	5.00	No.		
4	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed con- crete around pan removing the same carefully and stacking the serviceable materials as adn where directed including throwing the unserviceable materiasls out side etc. carefully and throwing out the refusal outside etc. complete.	4.00	No.		
5	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided,	2.00	Cum		

				Sector Sector	
	finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only.				
-	Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed				
6	sand VSI Grade) Providing and fixing 10cm C.I. Nahani Trap including C.I. grating bend and piece of C.I. pipe upto the outside face of the wall complete	7.00	No.		
7	Providing and fixing 1st class white glazed earthenware Orissa Type W.C. Pan 580 mm dia including P or S trap cast iron soil and vent pipe upto the outside face of the wall (1:5:1 0) cement concrete bedding 15 mm thick, 10 liter P.V.C. flushing cistern with all necessary pipe connection etc. complete	4.00	No.		
8	Providing water proof bedding for flooring of Bath and WC 25 mm thick in C.M. 1:3 including using approved water proofing compound in specified proportion as per manufacturers specifications for per bag of cement including leveling, curing and covering 10 years guarantee on court fee stamp paper of Rs.500/- including ponding test etc. complete.	31.00	Sqm		
9	Providing waterproof plaster in W.C. and bath 20 mm thick for dado in cement mortar 1:3 In Rs. with neat finishing, floating using waterproofing compound at the rate of 1 Kilogram. per bag of cement of approved make and manufacturer and curing (and filling joints of Nahani trap and any outlet by properly) etc. complete.	75.00	Sqm		
10	Providing and laying in position flooring of telephone black / Amba White / Cat bary brown / Ruby red / Ocean Brown granite stone of approved shade and size 18 mm to 20 mm thick on bed 1:6 cement mortar including cement floats striking joints, pointing in C.M. 1:3 curing and cleaning etc. complete	9.00	Sqm		
1					

· 6

	of having size 30 cm x 30 cm confirming to I.S.15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement				
12	slurry cleaning curing etc. complete. Providing and laying ceramic tiles having size 30 cm. x 45 cm. confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.	75.00	Sqm		
13	Providing and fixing coloured glazed earthenware Wash Hand Basin of 45 cm x 30 cm size including cold water pillar tap/cold and hot water pillar tap brackets, rubber plugs and brass chain, stop tap and necessary pipe connection including P.V.C. waste pipe and trap up to the outside face of the wall. Making good the damaged surface, testing etc. complete.	4.00	No.		
14	Providing and fixing fiber glass reinforced polyster door shutter 30 mm thick as per IS 14856 (2000) (Reaffirmed 2006) without ventilator including chromium plated fixtures and fastening with chromium plated handles on both sides, etc complete	9.00	Sqm	5	
15	Providing and constructing Brick Masonry Inspection Chamber 60cm x 45cm With R.C.C. raft in B.C. soil area including cost of reinforcement, 1:2:4 cement concrete channels half round G.S.W. pipes, Brick Masonry, plastering from inside and airtight 75 mm thick R.C.C. cover medium duty 100Kilogrametc. complete.	2.00	No.		
16	Providing and applying Royale Luxury Emulsion of approved make on internal wall surface In Rs. as detailed below Scrapping for surface with emery paper and wipe clean for area. wall primer with brush by adding mineral turpentine oil by 8 to 10 % or water by 15 to 20% allowing to dry for 6 to 8 hoursAfter applying Asian / Berger / Nerolac / Dulex Paints or equivalent acrylic wall putty with appropriate prpportion of water of allow to dry for period of 4 to 6 hours of activity. Scrapping with emery paper and	186.00	Sqm		

1q

			1	 1	
	wipe clean Applying paints Royale Luxury emulsion 1st coat with brush water content water 40 to 45% or 65 to 70% by role Applying paints Royale luxury emulsion 2nd coat with brush with water content 40 to 45 % or 65 to 70 % by roller. (With prior approval of S.E.				•
17	Providing and laying in trenches 15 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	25.00	Rmt		
18	Providing and laying in trenches 25 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete	20.00	Rmt		
19	Providing and fixing C.P. BIB cock with wall flange of approved make including necessary sockets/ union nut etc. complete.	5.00	No.		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				

