


## SNDT Women's University

1, Nathibai Thackersey Road,  
Mumbai 400 020  
Phone: +91 22 2203 1879  
Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ  
१, नाथीबाई ठाकरसी मार्ग  
मुंबई ४०० ०२०  
Telegram: UNIWOMEN  
Website: sndt.ac.in

Estate Section/2024-25/48

May 09<sup>th</sup>, 2024

### **SUB: Quotation for Development work of Parking Area for Vehicles at S.N.D.T. Women's University Pune campus.**

**Madam/Sir,**

Sealed quotations are invited for Quotation for Development work of Parking Area for Vehicles at S.N.D.T. Women's University Pune campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **20<sup>th</sup> May 2024** Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

#### **A) Technical Bid**

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

#### **B) Financial Bid**

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

**The University reserves the right to reject any or all quotations without assigning any reasons thereof.**

Regards,

Prof. Vilas D. Nandavadekar

(20)

Registrar  
SNDT Women's University  
Mumbai - 20.



**(Offer should filled on letter head)**  
**Annexure A**

To,

The Registrar,  
SNDT Women's University,  
Churchgate, Mumbai

**Sub: Quotation for Development work of Parking Area for Vehicles at S.N.D.T. Women's University Pune campus.**

**Respected Madam/Sir,**

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Excavation for foundation in earth, soils of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5m to 3.0m) By Manual Means	108.00	Cum.		
2	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	8.100	Cum.		
3	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete.	72.00	Sqm.		
4	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm	60.00	Cum.		



	including watering and compaction etc. complete.				
5	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	67.50	Cum.		
6	Providing and laying cement concrete pipe of IS 458:2003 NP-2 class of 600mm diameter in proper line, level and slope including providing and fixing collars in cement mortar 1:2 and curing etc. complete.	5.00	Rmt.		
7	Providing and laying Cast in situ/Ready Mixcement concrete in M20 of trap/granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	67.50	Cum.		
8	Finishing upto 225 mm thick cement concrete laid to proper level and slope including compacting finishing with tremix treatment for paving slab with compaction by screed vibrator , removing excess water from the cement concrete by tremix vaccum dewatering system , finishing the surface with floater and trowel including all etc. complete as directed	400.00	Sqm.		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				



