SNDT Women's University 1, Nathibai Thackersey Road, Mumbai 400 020 Phone: +91 22 2203 1879 Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ १, नाथीबाई ठाकरसी मार्ग मुंबई ४०० ०२० Telegram: UNIWOMEN Website: sndt.ac.in

June 02<sup>nd</sup>, 2025

Estate Section/2025-26/63

SUB:Quotation for Repairs and extension work of compound wall from Guest house bldg. to staff Quarter bldg. at S.N.D.T.W.U. Pune Campus

### Madam/Sir,

Sealed quotations are invited for Quotation for Quotation for Repairs and extension work of compound wall from Guest house bldg. to staff Quarter bldg. at S.N.D.T.W.U. Pune Campus. Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before  $10^{+7}$  June 2025 Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop. Envelop may contains following documents in respective envelop:

### A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

#### **B)** Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Shri. Rak Registrar (Addl. Charge)

# (Offer should filled on letter head) Annexure A

To,

The Registrar, SNDT Women's University, Churchgate, Mumbai

SUB:Quotation for Repairs and extension work of compound wall from Guest house bldg. to staff Quarter bldg. at S.N.D.T.W.U. Pune Campus.

# **Respected Madam/Sir,**

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Removing wire fencing with iron/ C.C. fencing post and stacking the materials as directed with all leads, lifts etc. complete.	216.00	Rmt.	alif versaan Malif versaan Malif versaan	
2	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	38.00	Cum	18951 (1877) - Arlen 2009	
	Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/ granite/quartzite/gneiss metal for plain or molded sills, cornice, jambs, block in course, or architraves of required size and shapes including				
3	steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided,finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly	14.00	Cum		
	laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer etc. complete, With			irt () olog Standar og	
	fine aggregate (Crushed sand VSI Grade) Providing sand faced plaster externally in cement				
4	mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	432.00	Sqm		
5	Providing and erecting 1.2 meter high wire	180.00	Rmt.		

P	on mild steel angle ( 50 x 50x 6mm) post at 2.5 m c/c including excavation of pits of foundation concrete fixing the posts in ( 1:4:8) cement concrete block of 45x45x45 cm and fastening the Wires and painting the angles with one coat with red lead primer and two coats of oil painting etc.complete	
	Total	
	Taxes will be paid at actual at the prevailing time.	
	Net Total	

