



**SNDT WOMEN'S UNIVERSITY**  
**1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020**

Estate Dept./2018-19/ (Not. 10)/202

November 15, 2018

**Sub: Quotation of Structural strengthening work of Pump room and Electrical room at ground floor in Hostel building at SNDT Women's University, Juhu Campus.**

**Madam/Sir,**

Sealed quotations are invited for Structural strengthening work of Pump room and Electrical room at ground floor in Hostel building at SNDT Women's University, Juhu Campus. Interested vendors are to be submit their quote in the format given as Annexure A on company letter head. Quotation should be submitted to The Office of The Registrar at Churchgate campus on or before 30<sup>th</sup> November 2018.

**The University reserves the right to reject any or all quotations without assigning any reasons thereof.**

*M24*  
*15.11.18*  
**(Dr. Meena Kute)**  
**Registrar (Addl. Charge)**



## SNDT WOMEN'S UNIVERSITY

1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020

(Offer should filled on letter head)

### Annexure A

To,  
The Registrar  
SNDT Women's University,  
Churchgate, Mumbai

**Sub: Quotation for Structural strengthening work of Pump room and Electrical room at ground floor in Hostel building at SNDT Women's University, Juhu Campus.**

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No	Description	Qty	Unit	Rate	Amount
1	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 meters or spreading in the compound and cleaning the site etc. complete.	150.00	Sqm		
2	Breaking/chipping carefully the loose concrete/plaster of distressed member without damaging existing strong concrete by means of sharp chissle which should tempered regularly or high frequency low impact hammers used, cleaning the surface by water jet pressure pump at 4 to 5 kg/sqcm. Pressure to remove chlorides and loose particles, air drying the surface etc, the work should be carried out with all the safety measures like helmet, safety belt supervision of qualified supervisor. (The damaged area of member/concrete will be measured) etc. complete. (Excluding all taxes)	115.00	Sqm		
3	Removing any kind of debris including loading in truck and conveying to approved dumping point beyond MCGM limits, unloading, spreading etc complete.	50.00	Cum		
4	Providing and applying of bond coat approved epoxy resin MasterBrase 1414 of BASF/EPI bond of Krishna Conchem/or equivalent before polymer plaster/concrete and new concrete/polymer bond between old concrete and new concrete/polymer plaster surface within half an hour of after	115.00	Sqm		



**SNDT WOMEN'S UNIVERSITY**  
**1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020**

Sr. No	Description	Qty	Unit	Rate	Amount
	application of bond coat conforming to ASTM C 881 Type 2, using nylon scaffolding labour etc complete. (excluding all taxes)				
5	Providing and applying 30mm thick polymer mortar to load carrying RCC member in two layers in proportion of 1:5:15 by weight of high dispersion polymer having solid content 37% +- 1% MasterEmaco SBR 2 of BASF/FOSROC/Krishna Conchem or equivalent approved make and quality, cement and Quartz sand with required water cement ratio for desired consistency and applying and finishing by floating, after curing initial setting time applying bonding coat for 2 <sup>nd</sup> coat etc as per manufactures specifications etc complete. (Excluding all taxes)	115.00	Sqm		
6	Providing and fixing in position HCRM / CRS (Corrosion Resistant Steel) bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. Including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.50	Metric Tonnes		
7	Providing and erecting steel self supported steel H-Frame Scaffolding with cross bracing of good quality without dents and corrosion to reach place of work including approaches, extension, working platform ladders, lifting tackle necessary wall achors for men and materials, till completion of all structural repair items of work and curing period etc complete. The work should be carried out with all the safety measures, like helmet, safety belt and adequate labour insurance under the supervision of qualified supervisor this item should be used only for structural repair work for entire period of building (payment should be only once irrespective of duration of scaffolding) etc completed. (Including all taxes) Engineer in charge.	250.00	Sqm		
	<b>Total Amount</b>				



**SNDT WOMEN'S UNIVERSITY**  
**1, Nathibai Thackersey Road, Churchgate, MUMBAI 400 020**

All the terms and conditions given in notifications are studied thoroughly and accepted fully.

Thanking You,

Yours Faithfully,

**Name of Company**

**Signature of the Proprietor**

**Date:**

**Note: Enclose GST number, PAN number, declaration if GST is not applicable.**

(Dr. Merita Kute)  
Registrar (Acad. Charge)